

Ref No.SZV1707076001

TEST REPORT

Product	: TYPE-C				
Model	:	/			
Client	:	SHENZHENZDTCONN TECHNOLOGY CO.,LTD			
Factory	:	/			
Test sort	:	Entrustment inspection			

Shenzhen Anbotek Compliance Laboratory Limited





Marking

- 1. The test report is invalid without the official stamp of test center.
- 2. Nobody is allowed to photocopy or partly photocopy this test report without written permission of test center.
- 3. The test report is invalid without the signatures of testing engineer, reviewer and approver.
- 4. The test report is invalid if altered.
- 5. Objections to the test report must be submitted to test center within 15 days.
- 6. The test report is valid for the tested samples only.
- 7. As for test verdict, "—"means "no need for judgment" "N/A" means "not applicable", "P" means "pass", "F" means "fail".







安博 检测

No.: SZV1707076001		Date: Jul. 28, 2017 Page 1 of 2	,			
Applicant	:	SHENZHENZDTCONNTECHNOLOGY CO.,LTD				
		Shenzhen City, Guangdong province, GuangmingNew district. Nisheda second				
Address	:	Dong industrial Zone43B Gongming				
Report on the submitted sample(s) said to be:						
Sample Name	:	TYPE-C				
Model	:	/				
Trademark	:	/				
Description	:	/				
Supplier	:	/				
Manufacturer	:	/				
Other information	:	The sample has been reflow				
Sample(s) received Date	:	Jul. 25, 2017				
Testing period	:	Jul. 25, 2017 to Jul. 28, 2017				
Test Result:						

Please refer to the next pages

Test Conclusion:

Section No.	Test Name	Test Method	Evaluation
1	IPX7	IEC 60529:2013	PASS



Name: Mike Jiang Title: Lab Manager

Prepared by:

arlos le

Name: Carlos Ye Title: Test Engineer

Name: Jimmy Zhou Title: Lab Manager







No.: SZV1707076001

Date: Jul. 28, 2017

Page 2 of 2

1 IDV7		, ,					
1.IPX7 Test Method	IEC 60529:2013						
Test Condition	Sample surface is at least 0.15m from the surface of the water, at least 1m depth of the sample. Test Time: 30min						
Test Equipment	Equipment Name	Equipment No.	Model	Validity Period			
	Water proof test system	SE-1154	GR-IPX8A	2017.08.23			
Test Result	Sample No.	Requirement	Test Result	Conclusion			
	SZV1707076-001	No water enter the sample inside or the water inside does not affect the electrical properties of the sample.	There is no water inside the sample	PASS			
Photos	Befo	re test	Test set-up				

End of Report

